

क्र. रटामराकौवि/२०२५-२६/कोपरी/Electrical/प्रशासन/३७४

दिनांक: 22 JUL 2025

दरपत्रक सूचना

विषय: रतन टाटा महाराष्ट्र राज्य कौशल्य विद्यापीठ, मुंबई अंतर्गत कोपरी ठाणे येथे इलेक्ट्रिकल काम करून घेणेबाबत.

रतन टाटा महाराष्ट्र राज्य कौशल्य विद्यापीठ, मुंबई यांचे कार्यालय एलफीस्टन महाविद्यालय येथे सुरु करण्यात आले आहे. रतन टाटा महाराष्ट्र राज्य कौशल्य विद्यापीठ अंतर्गत विविध अभ्यासक्रम सुरु करण्यात आले आहेत. विद्यापीठ अंतर्गत कोपरी ठाणे येथे इलेक्ट्रिकल काम करून घेण्याकरिता मा. कुलगुरु, रतन टाटा महाराष्ट्र राज्य कौशल्य विद्यापीठ, मुंबई यांच्या अनुमतीने संस्था/पुरवठादार यांचेकडून सिलबंद दरपत्रके मागविण्यात येत आहेत.

रतन टाटा महाराष्ट्र राज्य कौशल्य विद्यापीठ, मुंबई अंतर्गत कोपरी ठाणे येथे इलेक्ट्रिकल काम करून घेण्यासाठी आपले दरपत्रक मा. कुलसचिव, रतन टाटा महाराष्ट्र राज्य कौशल्य विद्यापीठ, मुंबई यांचे नावे दि. २९/०७/२०२५ दुपारी ०३.०० वाजेपर्यंत कार्यालयात पोहचतील अशा पद्धतीने पाठविण्यात यावीत, उशिरा प्राप्त झालेली दरपत्रके स्विकारण्यात येणार नाहीत.

दरपत्रकामध्ये दर नमूद करताना ते सर्व करासहीत, वाहतूक खर्च, लॉडिंग अनलॉडिंग आणि इतर तत्सम खर्चासह असावेत अथवा त्यामध्ये याबाबत स्पष्ट उल्लेख असावा तसेच सिलबंद पाकिटावर करावयाच्या कामाच्या बाबींचा आणि दरपत्रक सादरीकरणाचा अंतिम दिनांकाचा स्पष्ट उल्लेख असावा.

प्राप्त झालेल्या दरपत्रकांपैकी काही अथवा सर्व दरपत्रके नाकारण्याचा अधिकार राखून ठेवण्यात आला असून याबाबतचे कोणतेही कारण देणे बंधनकारक नाही.

प्राप्त झालेल्या दरापैकी कमी असलेल्या दरास काम देण्यात येईल. सदर काम द्यावयाचे सर्व अधिकार मा. कुलगुरु, रतन टाटा महाराष्ट्र राज्य कौशल्य विद्यापीठ, मुंबई यांनी राखून ठेवले आहेत.

रतन टाटा महाराष्ट्र राज्य कौशल्य विद्यापीठ, मुंबई विद्यापीठ, मुंबई अंतर्गत कोपरी ठाणे येथे इलेक्ट्रिकल काम करून घेण्यासाठीचे तपशील प्रपत्र १ मध्ये सोबत जोडण्यात आले आहे.



Stalwar
(डॉ. राजेंद्र तलवारे)

प्र. कुलसचिव
र.टा. म.रा.कौ. वि., मुंबई

Ratan Tata Maharashtra State Skills University, Mumbai

Location: Kopari Thane

Annexure - 1

Sr No	Item Description	Qty	Unit	Rate	Amount
A	DISTRIBUTION BOARDS				
	Supply, installation, testing, tagging, (Circuit numbering) and commissioning of following IP43, double door readymade recessed type MCB, DB, fabricated out of CRCA sheet and painted with powdercoating process OR made out of scratch proof polycarbonate body, and concealed in wall or on surface with necessary frame complete as required.	--	--	--	--
1	HVAC POWER DISTRIBUTION BOARD (HVACDB) 8way, TPN MCB Double Door DB Incomer :-100A TPN MCB, 10KA : 1Nos100A/300mA FP RCCB : 1Nos Outgoing :-20A DP MCB, 10KA : 12Nos.	2	Set		
2	LIGHTING DISTRIBUTION BOARD (LDB)12way, SPN MCB Double Door DB Incomer :-32A DP MCB, 10KA : 1Nos Outgoing :-6/10A SP MCB, 10KA : 10Nos.	2	Set		
B	L.T. CABLES & END TERMINATIONS				
1	Supply and laying of 1.1 KV grade PVC insulated, inner sheath PVC tapped extruded outer sheath PVC GI strip/round armoured, solid aluminium/Copper conductor power cable conforming to IS 1554 / Part -I with latest amendments fixed on wall / column slab etc.	--	--	--	--
1.1	4C X 6 sq mm Cu Armoured Cable	50	Mtrs.		
1.2	3.5C X 50 sq mm Alu Armoured Cable	50	Mtrs.		
2	End Joining of Cables Termination	--	--	--	--
2.1	4C X 6 sq mm Cu Armoured Cable	2	Nos.		
2.2	3.5C X 50 sq mm Alu Armoured Cable	2	Nos.		
C	EARTHING STATIONS				
1	4 sqmm Single core Flexibial Cablefor Earthing.	100	Mtrs.		
	POINT WIRING				
	POINT WIRING & FIXING OF POINTS	--	--	--	--



Sr No	Item Description	Qty	Unit	Rate	Amount
	Point wiring for Light / Ceiling Fan / 5A Socket outlet / 15 A Socket outlet/ Exhaust Fan/15A Power Plugs etc. switches of modular type mounting box with with 650/1100 volts grade as per IS694-1990 ISI marked multistranded copper conductor FRLS insulate wire etc.	--	--	--	--
1.1	Primary Light Point with 2x1.50 + 1 x1.00 Sq.mm wire and 6 Amp Switch complete with all accessories etc. (for maximum length up to 6 Mtrs.)	10	Nos.	1150.00	11500.00
1.2	Secondary or light point in group, with 2x1.50 + 1 x1.00 Sq.mm wire and 6 Amp Switch complete with all accessories etc. (for maximum length up to 4 Mtrs.)	10	Nos.	1000.00	10000.00
1.3	Ceiling Fan Point with 2x1.50 + 1 x1.00 Sq.mm wire and 6 Amp Switch complete with all accessories etc. (for maximum length up to 6 Mtrs.)	10	Nos.	1300.00	13000.00
E	CIRCUIT WIRING				
	Supply and laying of Mains Wiring in 25 mm. Dia MMS PVC surface conduit above false ceiling & concealed below inclusive all accessories and hardware, saddles / spacers etc., complete in all	--	--	--	--
1	LIGHTING CIRCUIT	--	--	--	--
1.1	2 x 2.5 Sq.mm + 1 x 1.5 Sq.mm E. Wire in 25mm PVC Pipe. (LDB Ckt)	100	Mtrs.		
1.2	2 x 2.5 Sq.mm + 1 x 1.5 Sq.mm E. Wire in 25mm PVC Pipe. (HVACDB Ckt)	500	Mtrs.		
1.3	3 x 4 Sq.mm + 1 x 2.5 Sq.mm Cu Wire in 25mm PVC Pipe. For AC ckt	500	Mtrs.		
1.4	AC box With 20 Amp DP Switch OR 32-63 Amp MCB industrial Socket	20	Nos.		
2	POWER SOCKETS	--	--	--	--
2.1	6 Amp 5 Pin Socket with 6 Amp Switch for RAW power.	20	Nos.		
2.2	16 Amp Combined Socket with 16 Amp Switch for Raw power	10	Nos.		
2.3	Supply and laying 25 mm MMS grade PVC Conduits with all accessories (or Casing Patti)	100	Mtrs.		
F	LIGHT FIXTURES & FAN FITTINGS				
1.1	Supply and Installation of 15W LED Down Light Fitting	4	Nos.		
1.2	Supply and Installation of 1200mm Suspended/Surface Mounted Aluminium Extruded Batten suitable for Industrial	20	Nos.		



Sr No	Item Description	Qty	Unit	Rate	Amount
1.3	Supply and Installation of 1200 MM double bearing energy saver Ceiling Fan)	10	Nos.		
1.4	Supply and Installation of 4' Fan rod , hook,clamp and Fasnut.	10	Nos.		
G	MESCELLANEOUS ITEM				
1.1	Supply of Rubber checkered mat of size 2000 x 1000 x 12 mm thick, 11000 V grade.	1	Nos.		
1.2	Labling for Switch plate and DB's	1	Nos.		
1.3	Removal of unwanted old wooden switch board & wiring	1	LS		
1.4	Cleaning & Painting of Existing Panel	1	LS		
	Basic cost				
	GST @ Extra 18%				
	Total				

Kindly Note :

1. GST No. is mandatory in quotation
2. Cost should be inclusive of installation, transportation, loading, unloading charges.
3. The prices listed for the aforementioned goods are good for six months after the work order date.
4. Delivery/installation location: Kopari, Thane
5. Billing address: Ratan Tata Maharashtra State Skills University, 1st Floor, Elphinstone Technical High School Metro Chowk, Nagarpalika Marg, Dhobi Talao, Chhatrapati Shivaji Terminus Area, Fort, Mumbai, Maharashtra 400001
6. PAN Details, Udyam Registration, any other certification/license attached with the quotation.



Salwa
Registrar (I/C)
RTMSSU, Mumbai