

क्र. रटामराकौवि/२०२५-२६/ठाणे/प्रशासन/१४०

दिनांक: 18 FEB 2026

दरपरत्रक सूचना

विषय: रतन टाटा महाराष्ट्र राज्य कौशल्य विद्यापीठ कोपरी ठाणे येथील केंद्राच्या पहिल्या मजल्यावर DMLT Lab तयार करणेबाबत.

रतन टाटा महाराष्ट्र राज्य कौशल्य विद्यापीठ, मुंबई यांचे कार्यालय एलफीस्टन महाविद्यालय येथे सुरु करण्यात आले आहे. रतन टाटा महाराष्ट्र राज्य कौशल्य विद्यापीठ अंतर्गत विविध अभ्यासक्रम सुरु करण्यात आले आहेत. विद्यापीठ अंतर्गत कोपरी ठाणे येथील केंद्रामधील पहिल्या मजल्यावर उपलब्ध असलेल्या जागेत DMLT laboratory तयार करून घेण्याकरिता मा. कुलगुरु, रतन टाटा महाराष्ट्र राज्य कौशल्य विद्यापीठ, मुंबई यांच्या अनुमतीने संस्था/पुरवठादार यांचेकडून सिलबंद दरपत्रके मागविण्यात येत आहेत.

रतन टाटा महाराष्ट्र राज्य कौशल्य विद्यापीठ, मुंबई अंतर्गत कोपरी ठाणे येथील केंद्रामधील पहिल्या मजल्यावर उपलब्ध असलेल्या जागेत DMLT laboratory तयार करून घेण्याकरिता आपले दरपत्रक मा. कुलसचिव, रतन टाटा महाराष्ट्र राज्य कौशल्य विद्यापीठ, मुंबई यांचे नावे दि. 20/02/2026 दुपारी 03.00 वाजेपर्यंत कार्यालयात पोहचतील अशा पद्धतीने पाठविण्यात यावीत, उशिरा प्राप्त झालेली दरपत्रके स्विकारण्यात येणार नाहीत.

दरपत्रकामध्ये दर नमूद करताना ते सर्व करासहीत, वाहतूक खर्च, लॉडींग अनलोडींग आणि इतर तत्सम खर्चासह असावेत अथवा त्यामध्ये याबाबत स्पष्ट उल्लेख असावा तसेच सिलबंद पाकिटावर करावयाच्या कामाच्या बाबींचा आणि दरपत्रक सादरीकरणाचा अंतिम दिनांकाचा स्पष्ट उल्लेख असावा.

प्राप्त झालेल्या दरपत्रकांपैकी काही अथवा सर्व दरपत्रके नाकारण्याचा अधिकार राखून ठेवण्यात आला असून याबाबतचे कोणतेही कारण देणे बंधनकारक नाही.

प्राप्त झालेल्या दरापैकी कमी असलेल्या दरास काम देण्यात येईल. सदर काम द्यावयाचे सर्व अधिकार मा. कुलगुरु, रतन टाटा महाराष्ट्र राज्य कौशल्य विद्यापीठ, मुंबई यांनी राखून ठेवले आहेत.

रतन टाटा महाराष्ट्र राज्य कौशल्य विद्यापीठ, मुंबई विद्यापीठ, मुंबई अंतर्गत कोपरी ठाणे येथील केंद्रामधील पहिल्या मजल्यावर उपलब्ध असलेल्या जागेत DMLT laboratory तयार करून घेण्यासाठीचे तपशील प्रपत्र १ मध्ये सोबत जोडण्यात आले आहे.



(Signature)
(डा. राजेंद्र तलवारे)

प्र. कुलसचिव,
र.टा. म.रा.कौ. वि., मुंबई

पहिला मजला, एल्फिस्टन हायस्कूल, ३ महापालिका मार्ग, मेट्रो चौक, मुंबई - ४०० ००९.

Email id: contact@mssu.ac.in

Ratan Tata Maharashtra State Skills University, Mumbai

Annexure 1

Detailed specification for work at Kopari Thane

Sr. No.	Item of Work	Quantity	Unit	Rates in Rs.	Amount in Rs.
1	Partition Work				
	Providing & Fixing in position, Acoustical Ceiling made from Gypsum Plain Panels on approved heavy duty G.I. frame ceiling channels at 450 c to c, & intermediate channels not more than 1200 c to c, along with plywood forms suspended with Hangers from Roof, in front of 1000Gsm synthetic wool 50mm thick, with Paint, including cost of required Cut-Outs, decorative mouldings / finishing-items & Scaffolding, as per Architectural & Acoustical Design & Instructions & Complete in all aspects. including all materials labour, finishing etc. complete	98.93	Sq M		
2	Jamb Door				
	Providing and laying Telephone Black / Amba White / Cadbury Brown / Ruby Red / Ocean Brown granite stone of 18 to 20 mm thickness for door frame/dado/window boxing etc. on C.M. 1:6, including filling joints with polymer base filler, nosing/moulding the sharp edges wherever necessary, curing etc. complete.	1.56	Sq M		
3	Internal Paint				
	Providing and applying plastic emulsion paint of approved quality, colour and shade to new surface in three coats, including scaffolding and preparing the surface (excluding primer coat) etc. complete.	395.70	Sq m		
	Ceiling paint	32.19	Sq m		
4	False ceiling				
	Providing and fixing false ceiling of plain as best oscement sheets 4mm thick with teakwood beadings 45x12mm with frame work of teakwood battens of size 70x60mm at 1.00M center to center including scaffolding, if necessary, all iron work and painting (visible surfaces) to A.C. sheet and beading in two coats etc. complete	32.24	Sq m		
5	Punning				
	Providing and applying Two coats of wall care Putty on plastered surface and Ceiling and Walls to prepare surface even and smooth of approved make, etc. complete.	395.70	Sq m		
6	Glass Door				
	Providing and fixing solid core flush door shutter in single leaf, 32 mm thick, decorative type of exterior grade as per detailed drawings, with approved face veneers 3 mm thick on both faces or as directed, all necessary beads, mouldings and lipping, wrought iron holdfasts, chromium plated fixtures and fastenings, with brass mortise lock and chromium plated handles on both sides, and finishing with French polish etc. complete.	2.52	Sqm		
7	Platform with sink				
	Providing and preparing kitchen otta up to 75 cm width, made up from 30 mm thick and 75 cm high vertical support for kadppa at 1m.c/c of 25mm thick both side polished kadappa middle shelf and bottom of 20mm thick one side polished kadappa with facia patti of 20x50mm kadappa including all material labour cutting fixing with	3.75	Sqm		



Sr. No.	Item of Work	Quantity	Unit	Rates in Rs.	Amount in Rs.
	cement mortar and araldite curing polished and cleaning etc. complete.				
	Tile below platform				
	Providing and laying ceramic tiles of having size 30cm. x 30cm. and confirming to corresponding I.S. for dado and skirting in required position with ready made adhesive mortar of approved quality on plaster of 1:2 cement mortar including 1:2 cement mortar including joint filling with white /colour cement slurry cleaning curing etc. complete	6.33	Sqm		
	Tile above platform				
	Providing and laying ceramic tiles of having size 30cm. x 30cm. and confirming to corresponding I.S. for dado and skirting in required position with readymade adhesive mortar of approved quality on plaster of 1:2 cement mortar including 1:2 cement mortar including joint filling with white/colour cement slurry cleaning curing etc. complete	6.33	Sqm		
8	Stainless Steel sink of size 600*510*200mm of nirali or equivalent make	1.00	No.		
9	Flooring				
	Providing and laying machine cut machine Polished Kota stone flooring 25mm to 30mm thick and required width in plain /diamond patten non bed of 1:6 C.M. including cement float, filling joints with neat cement slurry, curing, polishing and cleaning etc complete	42.49	Sqm		
10	C.P.pillar cock long neck with aerator jaquar make continental (Cat.No. CON- 021)	1.00	No.		
11	Civil Costing				
12	Plumbing (2%)				
13	Electrical as per task (7%)				
14	Total lab work costing (10+11+12)				
Total					
GST in Rs.					
Total including GST in Rs.					

Note:-

1. All the prices including Supply and Loading unloading.
2. These rates are valid for 1 year for any additional requirements if any.
3. GST will be extra as per applicable
4. Quantity: The quantity of materials and services required is based on your provided details and may change based on actual site measurements or requirements.
5. Final payment will be as per the actual work done.



Stalwar
18/07/26
Registrar I/C

Ratan Tata Maharashtra State Skills University