

क्र. रतामराकौवि/२०२६-२७/ठाणे/प्रशासन/६१

दिनांक: २२/०४/२०२६

## दरपरत्रक सूचना

विषय: रतन टाटा महाराष्ट्र राज्य कौशल्य विद्यापीठ कोपरी ठाणे येथील केंद्राच्या पहिल्या मजल्यावर DMLT Lab तयार करणेबाबत.

रतन टाटा महाराष्ट्र राज्य कौशल्य विद्यापीठ, मुंबई यांचे कार्यालय एलफीस्टन महाविद्यालय येथे सुरु करण्यात आले आहे. रतन टाटा महाराष्ट्र राज्य कौशल्य विद्यापीठ अंतर्गत विविध अभ्यासक्रम सुरु करण्यात आले आहेत. विद्यापीठ अंतर्गत कोपरी ठाणे येथील केंद्रामधील पहिल्या मजल्यावर उपलब्ध असलेल्या जागेत DMLT laboratory तयार करून घेण्याकरिता मा. कुलगुरु, रतन टाटा महाराष्ट्र राज्य कौशल्य विद्यापीठ, मुंबई यांच्या अनुमतीने संस्था/पुरवठादार यांचेकडून सिलबंद दरपत्रके मागविण्यात येत आहेत.

रतन टाटा महाराष्ट्र राज्य कौशल्य विद्यापीठ, मुंबई अंतर्गत कोपरी ठाणे येथील केंद्रामधील पहिल्या मजल्यावर उपलब्ध असलेल्या जागेत DMLT laboratory तयार करून घेण्याकरिता आपले दरपत्रक मा. कुलसचिव, रतन टाटा महाराष्ट्र राज्य कौशल्य विद्यापीठ, मुंबई यांचे नावे दि. ३०/०४/२०२६ दुपारी ०३.०० वाजेपर्यंत कार्यालयात पोहचतील अशा पद्धतीने पाठविण्यात यावीत, उशिरा प्राप्त झालेली दरपत्रके स्विकारण्यात येणार नाहीत.

दरपत्रकामध्ये दर नमूद करताना ते सर्व करासहीत, वाहतूक खर्च, लॉर्डिंग अनलॉर्डिंग आणि इतर तत्सम खर्चासह असावेत अथवा त्यामध्ये याबाबत स्पष्ट उल्लेख असावा तसेच सिलबंद पाकिटावर करावयाच्या कामाच्या बाबींचा आणि दरपत्रक सादरीकरणाचा अंतिम दिनांकाचा स्पष्ट उल्लेख असावा.

प्राप्त झालेल्या दरपत्रकांपैकी काही अथवा सर्व दरपत्रके नाकारण्याचा अधिकार राखून ठेवण्यात आला असून याबाबतचे कोणतेही कारण देणे बंधनकारक नाही.

प्राप्त झालेल्या दरापैकी कमी असलेल्या दरास काम देण्यात येईल. सदर काम द्यावयाचे सर्व अधिकार मा. कुलगुरु, रतन टाटा महाराष्ट्र राज्य कौशल्य विद्यापीठ, मुंबई यांनी राखून ठेवले आहेत.

रतन टाटा महाराष्ट्र राज्य कौशल्य विद्यापीठ, मुंबई विद्यापीठ, मुंबई अंतर्गत कोपरी ठाणे येथील केंद्रामधील पहिल्या मजल्यावर उपलब्ध असलेल्या जागेत DMLT laboratory तयार करून घेण्यासाठीचे तपशील प्रपत्र १ मध्ये सोबत जोडण्यात आले आहे.



(डॉ. राजेंद्र तलवारे)

प्र. कुलसचिव,

र.टा. म.रा.कौ. वि., मुंबई

**Ratan Tata Maharashtra State Skills University, Mumbai**

**Annexure 1**

Detailed specification for work at Kopari Thane

Sr. No.	Item of Work	Quantity	Unit	Rates	Amount
<b>1</b>	<b>Partition Work</b>				
	Providing and fixing in position partition made with 12 mm thick gypsum boards on both sides, fixed over 50 × 50 mm Sal wood framework at 600 × 600 mm center-to-center, with 50 mm thick, 800 GSM synthetic wool insulation in between, including cost of required cut-outs, scaffolding, and finishing, as per architectural and acoustical design and instructions, complete in all respects including all materials and labour, etc., complete.	44.00	Sq M		
<b>2</b>	<b>Jamb Door</b>				
	Providing and laying Telephone Black / Amba White / Cadbury Brown / Ruby Red / Ocean Brown granite stone of 18 to 20 mm thickness for door frame/dado/window boxing etc. on C.M. 1:6, including filling joints with polymer base filler, nosing/moulding the sharp edges wherever necessary, curing etc. complete.	3.12	Sq M		
<b>3</b>	<b>Aluminium Skirting at Partition</b>				
	<b>Aluminum Skirting:</b> Providing and fixing 100mm high aluminum skirting (1.5mm thick) with powder coating/anodized finish. Includes fixing to partitions, mitering corners, and silicon sealing at the floor level.	24.00	Rmt		
<b>4</b>	<b>Internal Paint</b>				
	Providing and applying plastic emulsion paint of approved quality, colour and shade to new surface in three coats, including scaffolding and preparing the surface (excluding primer coat) etc. complete.	182.00	Sq m		
<b>5</b>	<b>Ceiling Paint</b>				
	Providing and applying plastic emulsion paint of approved quality, colour and shade to new surface in three coats, including scaffolding and preparing the surface (excluding primer coat) etc. complete.	52.80	Sq m		
<b>6</b>	<b>Punning</b>				
	Providing and applying Two coats of wall care Putty on plastered surface and Ceiling and Walls to prepare surface even and smooth of approved make, etc complete.	72.00	Sq m		
<b>7</b>	<b>Primer Coat</b>				
	Interior Wall Primer: Applying one coat of acrylic water-based primer on new or old masonry surfaces. Includes surface preparation, sanding, and cleaning.	72.00	Sq m		
<b>8</b>	<b>Platform in Granite</b>				

Sr. No.	Item of Work	Quantity	Unit	Rates	Amount
	“Providing and constructing granite kitchen platform with fixing of stainless steel sink of size 600 mm × 450 mm, as per detailed drawings, including vertical Kadappa stone supports 25 mm to 30 mm thick, polished on both sides; Kadappa top 35 mm to 40 mm thick; and polished granite slab 16 mm to 20 mm thick for the top, with granite side strips at the front and both sides of the platform. The platform shall be raised with two vertical granite supports of 15 cm height and a top granite slab of size 75 cm × 40 cm, including cutting and providing opening for sink of required size in Kadappa as well as granite, etc., complete. (Platform top size: 5.00 m × 0.60 m and height: 0.75 m).”	7.26	Rmt		
9	<b>Tile below platform</b>				
	Providing and laying ceramic tiles of size 30 cm × 30 cm, conforming to the corresponding I.S. standards, for dado and skirting in the required position, fixed with ready-made adhesive mortar of approved quality over plaster in cement mortar 1:2, including joint filling with white or coloured cement slurry, cleaning, curing, etc., complete.	9.35	SQM		
10	<b>Tile above platform</b>				
	Providing and laying ceramic tiles of size 30 cm × 30 cm, conforming to the corresponding I.S. standards, for dado and skirting in the required position, fixed with ready-made adhesive mortar of approved quality over plaster in cement mortar 1:2, including joint filling with white or coloured cement slurry, cleaning, curing, etc., complete.	6.60	SQM		
11	<b>Stainless Steel sink</b>				
	Stainless Steel sink of size 600*510*200mm of niralii or equivalent make	1	No.		
12	<b>Flooring</b>				
	Tiling: 605mm x 590mm Stone-finish Vitrified tiles (Anti-skid) laid on CM 1:4. Includes joint filling with BAL Grout, 100mm high skirting, and maintaining proper slope.	110.92	SQM		
13	<b>C.P.pillar cock long neck with aerator jaquar make continental (Cat.No. CON- 021)</b>	1	No.		
14	<b>Sliding Door - Flush Vision Panel</b>				
	Providing and fixing sliding door with integrated 6mm toughened glass flush vision panel. Includes top track, rollers, recessed handles, and laminate finish.	2.88	SQM		
15	<b>Sliding Door - Flush Vision Panel-fixture</b>				
	<b>Sliding Door Hardware Set:</b> Supply and fixing of heavy-duty hardware set	1.00	No		
16	<b>Pelmet at hide sliding channel</b>	1.00	No		
17	<b>Vertical Granite</b>	2.00	SQM		
18	<b>Circular cut out 3 inch dia on both platform</b>				
	<b>Circular Core Cutting:</b> Making a 3-inch (75mm) dia. hole in granite/stone platform using a diamond core bit, including smooth finishing of edges and disposal of debris.	2.00	Ls		
19	<b>Bituminous patta filling at the roof</b>				

Sr. No.	Item of Work	Quantity	Unit	Rates	Amount
	"Providing waterproofing treatment as per IS: 1346–1966 to generally inaccessible sloping reinforced cement concrete terrace slab with bitumen felts in all positions in five courses, consisting of applying cold bitumen primer coat at the rate of 2.5 litres per 10 sq.m; hot bitumen layer at the rate of 14.5 kg per 10 sq.m; and over the same, laying bitumen felt of Type III Grade (I) as per IS: 1322–1965 across the slope with 10 cm overlap, commencing at the lowest level; again applying hot bitumen coat at the rate of 14.5 kg per 10 sq.m; and finally spreading grit at the rate of 14.5 kg per 10 sq.m; including all lifts, leads, and scaffolding wherever necessary, complete as directed, with four years' guarantee on requisite stamp paper, etc., complete."	10.80	Sq m		
<b>20</b>	<b>Door to the back of the lab</b>				
	Providing and fixing 40mm thick door shutter with vision panel	2.88	Sq m		
<b>21</b>	<b>Swing door Fixtures</b>				
	Swing Door Fixture Set: Heavy-duty hardware	1.00	No		
<b>12</b>	<b>Civil Costing</b>				
<b>13</b>	<b>Plumbing ( 2%)</b>				
<b>14</b>	<b>Electrical as per task ( 7%)</b>				
	<b>Total lab work costing</b>				
	GST 18 %				
	<b>Total</b>				

**Note:-**

1. All the prices including Supply and Loading unloading.
2. These rates are valid for 1 year for any additional requirements if any.
3. GST will be extra as per applicable
4. Quantity: The quantity of materials and services required is based on your provided details and may change based on actual site measurements or requirements.
5. Final payment will be as per the actual work done.



Registrar I/C

Ratan Tata Maharashtra State Skills University