

क्र. र.टा.म.रा.कौ.वि./२०२६-२७/ठाणे/प्रशासन/१५

दिनांक: 30 APR 2026

दरपत्रक सूचना

विषय: रतन टाटा महाराष्ट्र राज्य कौशल्य विद्यापीठ, मुंबई अंतर्गत कोपरी ठाणे येथील केंद्रामधील पहिल्या मजल्यावर महिला व पुरुष यांचे स्वच्छता गृहाचे नूतनीकरण करणेबाबत.

रतन टाटा महाराष्ट्र राज्य कौशल्य विद्यापीठ, मुंबई यांचे कार्यालय एलफीस्टन महाविद्यालय येथे सुरु करण्यात आले आहे. रतन टाटा महाराष्ट्र राज्य कौशल्य विद्यापीठ अंतर्गत विविध अभ्यासक्रम सुरु करण्यात आले आहेत. विद्यापीठ अंतर्गत कोपरी ठाणे येथील केंद्रामधील पहिल्या मजल्यावर महिला व पुरुष यांचे स्वच्छता गृहाचे नूतनीकरण करण्याकरिता मा. कुलगुरु, रतन टाटा महाराष्ट्र राज्य कौशल्य विद्यापीठ, मुंबई यांच्या अनुमतीने संस्था/पुरवठादार यांचेकडून सिलबंद दरपत्रके मागविण्यात येत आहेत.

रतन टाटा महाराष्ट्र राज्य कौशल्य विद्यापीठ, मुंबई अंतर्गत कोपरी ठाणे येथील केंद्रामधील पहिल्या मजल्यावर महिला व पुरुष यांचे स्वच्छता गृहाचे नूतनीकरण करण्याकरिता आपले दरपत्रक मा. कुलसचिव, रतन टाटा महाराष्ट्र राज्य कौशल्य विद्यापीठ, मुंबई यांचे नावे दि. ११/०५/२०२६ दुपारी ०३.०० वाजेपर्यंत कार्यालयात पोहचतील अशा पद्धतीने पाठविण्यात यावीत, उशिरा प्राप्त झालेली दरपत्रके स्विकारण्यात येणार नाहीत.

दरपत्रकामध्ये दर नमूद करताना ते सर्व करासहीत, वाहतूक खर्च, लॉडिंग अनलोडिंग आणि इतर तत्सम खर्चासह असावेत अथवा त्यामध्ये याबाबत स्पष्ट उल्लेख असावा तसेच सिलबंद पाकिटावर करावयाच्या कामाच्या बाबींचा आणि दरपत्रक सादरीकरणाचा अंतिम दिनांकाचा स्पष्ट उल्लेख असावा.

प्राप्त झालेल्या दरपत्रकांपैकी काही अथवा सर्व दरपत्रके नाकारण्याचा अधिकार राखून ठेवण्यात आला असून याबाबतचे कोणतेही कारण देणे बंधनकारक नाही.

प्राप्त झालेल्या दरापैकी कमी असलेल्या दरास काम देण्यात येईल. सदर काम द्यावयाचे सर्व अधिकार मा. कुलगुरु, रतन टाटा महाराष्ट्र राज्य कौशल्य विद्यापीठ, मुंबई यांनी राखून ठेवले आहेत.

रतन टाटा महाराष्ट्र राज्य कौशल्य विद्यापीठ, मुंबई विद्यापीठ, मुंबई अंतर्गत कोपरी ठाणे येथील केंद्रामधील पहिल्या मजल्यावर महिला व पुरुष यांचे स्वच्छता गृहाचे नूतनीकरण करण्यासाठी तपशील प्रपत्र १ मध्ये सोबत जोडण्यात आले आहे.


(डा. राजेंद्र तलवारे)

प्र. कुलसचिव,
र.टा. म.रा.कौ. वि., मुंबई

Ratan Tata Maharashtra State Skills University, Mumbai

Annexure 1

Detailed specification for renovation of Bathrooms at Kopari Thane

Sr. No.	Item of Work	QTY	SSR Unit	SSR Rates	Amount
1	Cleaning				
	Machine polishing to cement/marble mosaic tiled flooring or any other type of flooring including cleaning, washing, etc. complete.	230	Sq. Mtr.		
2	Internal Painting				
	Providing and applying two coats of synthetic enamel paint of approved colour to new/old structural steelwork and woodwork in buildings, including scaffolding if necessary, cleaning and preparing the surface (excluding primer coat) etc. complete.	162	Sq. Mtr.		
3	Washbasin				
	Providing and fixing White glazed with bottle trap earthenware Wash Hand Basin of 55x40 cm size including cold water pillar taps, brackets, rubber plugs and brass chain, stop tap, chromium plate bottle trap and necessary pipe connections including UPVC waste pipe and trap up to the outside face of the wall, making good the damaged surface, testing etc. complete.	6	No.		
4	Nahani trap				
	Sanitary Drainage Specification Providing and fixing 8 cm C.I. Nahani Trap including C.I. grating, bend, and piece of C.I. pipe up to the outside face of the wall complete.	2	No.		
5	Tap				
	Providing and fixing Auto closing pillar cock of pressmatic tap of approved make or equivalent including all fixtures, fittings etc. complete.	15	No.		
5	Aluminium Louvers				
	Providing and fixing in position powder coated aluminium louvered windows/ventilator of various sizes with powder coating as per detailed drawing and specifications including aluminium frames 80 x 38 mm x 1.22 mm box type, 5 mm thick sheet glass louvers, of approved make including all necessary accessories, weather stripping, and installation.	6.5	Sq. Mtr.		
6	Grill work				

Sr. No.	Item of Work	QTY	SSR Unit	SSR Rates	Amount
	Providing and fixing mild steel grillwork for windows, ventilators etc. 20 Kilogram/Square Metre as per drawing including fixtures, necessary welding and painting with one coat of anti-corrosive paint and two coats of oil painting complete.	6.5	Sq. Mtr.		
7	Mirror				
	Vanity Mirror size 0.6*1.2 m with edge Polising & mounted on wall with Plywood backing	6	Nos.		
8	Door				
	Reparing of all toilet doors	12	LS		
9	Debris Removal				
	Clearing and transporting debris from toilet blocks to a designated site. Includes cleaning of floors and stairways after removal.	1	Trip		
10	Door Closer				
	Hydraulic Door Closer: Supply and installation of ISI marked overhead hydraulic door closer (standard size) with silver finish. Includes testing for smooth closing and necessary hardware for mounting on	6	No		
11	Tile Dado (POP& Principal Room window wall only)				
	Providing and laying vitrified stone effect finish tiles of size 590 mm to 605 mm x 590 mm to 605 mm, 8 to 10 mm thick, conforming to I.S. 15622:2006 (Group B1a), of approved make, shade, and pattern, for dado and skirting in the required position, fixed in cement mortar 1:4, including neat cement float, filling joints, curing, and cleaning, etc., complete	20.394	Sq. Mtr.		
12	Punning				
	Providing and applying Two coats of wall care Putty on plastered surface and Ceiling and Walls to prepare surface even and smooth of approved make, etc complete.	33.99	Sq. Mtr.		
13	Painting				
	Providing and applying plastic emulsion paint of approved quality, colour and shade to new surface in three coats including scaffolding, preparing the surface. (excluding primer coat) etc. complete.	33.99	Sq. Mtr.		
20	Flush Tank				
	PVC Flushing Cistern: Supply and fixing of 10-liter PVC flushing cistern (White) with ISI mark, including all internal fittings, flush pipe, wall brackets, and 15mm CP angle valve with flexible connection.	6	No		
A	Civil Costing				

Sr. No.	Item of Work	QTY	SSR Unit	SSR Rates	Amount
B	Plumbing (8%) Note-Its Subject to changed as per site condition				
C	Electrical as per task (7%)				
	Total 3TOILET work costing (A+B+C)				
	GST 18%				
	Total				

Note:-

1. All the prices including Supply and Loading unloading.
2. These rates are valid for 1 year for any additional requirements if any.
3. GST will be extra as per applicable
4. Quantity: The quantity of materials and services required is based on your provided details and may change based on actual site measurements or requirements.
5. Final payment will be as per the actual work done.


Registrar I/C

Ratan Tata Maharashtra State Skills University